


- NOTES:
- 1) TWIN OAK LANE AND TAZEWELL PIKE TO BE WIDENED WITH LEFT TURN LANE ONTO TWIN OAK LANE, AND EXTENDED DECELERATION LANE FOR GIBBS SCHOOLS.
  - 2) ACCESS TO ALL UNITS FROM INTERNAL ROAD SYSTEM ONLY. LOTS 1-9 ACCESS FROM ROAD "E" ONLY.
  - 3) PERIPHERAL SETBACK OF 25 FEET APPLIES TO PERIMETER OF SUBDIVISION, EXCEPT ALONG TWIN OAK LANE WHICH HAS A PERIPHERAL SETBACK OF 20 FEET DUE TO LIMITED PROPERTY WIDTH.
  - 4) SIDEWALKS TO BE PROVIDED ALONG ROAD "A" FROM INTERSECTION WITH ROAD "E" TO ROAD "C" WITH PEDESTRIAN CONNECTION FROM ROAD "C" TO EDWARDS PLACE BETWEEN LOTS 73 & 74.
  - 5) SIDEWALKS TO BE PROVIDED ALONG ROAD "E" FROM INTERSECTION WITH ROAD "A" TO GREENWAY TRAIL CONNECTING TO GIBBS ELEMENTARY SCHOOL.
  - 6) EASEMENTS TO BE GRANTED FOR FUTURE KNOX COUNTY GREENWAY TRAIL ALONG BEAVER CREEK AS SHOWN.

Certification of Concept Plan.  
I hereby certify that I am a registered engineer, licensed to practice engineering under the laws of the State of Tennessee. I further certify that the plan and accompanying drawings, documents and statements conform to all applicable provisions of the Knoxville-Knox County Subdivision Regulations except as has been itemized and described in a report filed with the Metropolitan Planning Commission.

Registered Engineer: Garrett M. Tuck  
Tennessee Certificate No. 104281



LOCATION MAP

ALTERNATE DESIGN STANDARDS REQUIRING PLANNING COMMISSION APPROVAL:

- 1) REDUCTION OF MINIMUM CURVE RADIUS ON ROAD "A" AT STATION 10+89 FROM 250' TO 150'
- 2) REDUCTION OF MINIMUM CURVE RADIUS ON ROAD "A" AT STATION 22+39 FROM 250' TO 150'
- 3) REDUCTION OF MINIMUM CURVE RADIUS ON ROAD "E" AT STATION 59+33 FROM 250' TO 100'
- 4) REDUCTION OF MINIMUM CURVE RADIUS ON ROAD "E" AT STATION 60+83 FROM 250' TO 100'
- 5) REDUCTION OF DEPTH DOUBLE FRONTAGE LOTS 1-9 FROM 135 FEET TO MINIMUM OF 100 FEET.
- 6) REDUCTION OF MINIMUM CURVE RADIUS ON ROAD "E" AT STATION 47+22 FROM 250' TO 100'

VARIANCES:

- 1) REDUCTION OF TANGENT LENGTH BETWEEN BROKENBACK CURVES ON ROAD "E" FROM 150' TO 32.31'
- 2) REDUCTION OF TANGENT LENGTH BETWEEN REVERSE CURVES ON ROAD "A" FROM 50' TO 33.06'
- 3) REDUCTION OF MINIMUM TANGENT LENGTH BETWEEN BROKEN BACK CURVES A-2 AND A-3 FROM 150 FEET TO 114.48 FEET.

OWNER/DEVELOPER:  
HIGHWAY MARKINGS/ PAUL G. HIBBEN  
8333 COPPOCK ROAD  
KNOXVILLE, TN 37938  
PHONE: (865) 922-1550  
FAX: (865) 922-9229

ENGINEER:  
ROBERT G. CAMPBELL  
AND ASSOCIATES  
7523 TAGGART LANE  
KNOXVILLE, TN 37938  
PHONE: (865) 947-5996  
FAX: (865) 947-7556

CLT MAP: 021  
PARCELS: 001 & 013

DEED REFERENCE: 20051229-0056068  
DEED REFERENCE: 20150917-0017914

PROPERTY ZONED: PR (<4 DU/AC)



NUMBER OF LOTS: 107

TOTAL AREA: 33.04 ACRES

Revised: 8/1/2020

PLANNING SERVICES MPC FILE NUMBER:  
8-SA-20-C & 8-B-20-UR

NOTE: 25' PERIPHERAL SETBACK APPLIES AROUND SUBDIVISION PERIMETER. 20' PERIPHERAL SETBACK FROM TWIN OAK LANE FOR LOTS 1-9



| CURVE DATA   |  |  |   |
|--|--|--|---|
| CURVE A1<br>P.I. 10+86.46<br>PC 10+26.49<br>PT 11+40.59<br>A 43° 34' 57" (LT)<br>D 38° 11' 50"<br>R 150.000<br>L 114.10<br>T 59.97 | CURVE A2<br>P.I. 13+57.78<br>PC 12+90.00<br>PT 14+25.37<br>A 30° 20' 17" (RT)<br>D 22° 55' 06"<br>R 100.000<br>L 132.37<br>T 67.78 | CURVE E1<br>P.I. 59+33.33<br>PC 57+64.05<br>PT 61+12.05<br>A 118° 51' 20" (RT)<br>D 57° 17' 45"<br>R 100.000<br>L 207.44<br>T 169.28 | CURVE E2<br>P.I. 60+63.92<br>PC 60+03.80<br>PT 61+12.05<br>A 62° 01' 59" (RT)<br>D 57° 17' 45"<br>R 100.000<br>L 108.27<br>T 60.13  |
| CURVE A3<br>P.I. 15+95.10<br>PC 15+36.85<br>PT 16+51.31<br>A 26° 13' 50" (RT)<br>D 22° 55' 06"<br>R 100.000<br>L 114.45<br>T 58.25 | CURVE A4<br>P.I. 18+27.19<br>PC 18+00.47<br>PT 18+51.31<br>A 12° 12' 04" (LT)<br>D 22° 55' 06"<br>R 100.000<br>L 53.24<br>T 26.12  | CURVE E3<br>P.I. 47+22.04<br>PC 45+85.43<br>PT 47+13.21<br>A 107° 35' 30" (LT)<br>D 57° 17' 45"<br>R 100.000<br>L 187.78<br>T 136.61 | CURVE A5<br>P.I. 22+39.12<br>PC 20+83.43<br>PT 23+24.64<br>A 92° 08' 02" (LT)<br>D 38° 11' 50"<br>R 150.000<br>L 241.21<br>T 155.69 |

| NO.       | DATE | DESCRIPTION | BY | CHK. |
|-----------|------|-------------|----|------|
| REVISIONS |      |             |    |      |




ROBERT G. CAMPBELL & ASSOC., L.P.  
CONSULTING ENGINEERS  
KNOXVILLE, TENNESSEE

TWIN OAK LANDING  
CONCEPT PLAN / USE ON REVIEW

GENERAL LAYOUT

|                    |                   |                    |                    |
|--------------------|-------------------|--------------------|--------------------|
| DESIGNED BY<br>GMT | CHECKED BY<br>RGC | SCALE<br>1" = 100' | SHEET ONE<br>NO. 1 |
| DRAWN BY<br>JER    | DATE<br>8-1-20    | FILE NO.<br>15041  | OF 13 SHEETS       |







| LEGEND         |                               |
|----------------|-------------------------------|
| SF * SF * SF * | SILT FENCE                    |
| CE             | CONSTRUCTION EXIT             |
| IP             | STORM DRAIN INLET PROTECTION  |
| OP             | STORM DRAIN OUTLET PROTECTION |
| MA             | EROSION CONTROL MATTING       |
| CD             | ROCK CHECK DAM                |
| ---            | EXISTING GRADE                |
| 1150           | PROPOSED GRADE                |
| IP             | IRON PIN FOUND                |
| PIPE           | PIPE FOUND                    |
| G.V.           | GAS VALVE                     |
| W.M.           | WATER METER                   |
| MANHOLE        | MANHOLE                       |
| SIGN           | SIGN                          |
| W.V.           | WATER VALVE                   |
| FIRE HYDRANT   | FIRE HYDRANT                  |
| P/T            | POWER/TELEPHONE               |
| GUY WIRE       | GUY WIRE                      |

CONSTRUCTION SEQUENCE

PHASE 2:

- 1) CONSTRUCT PONDS #2, 3, & 4.  
INSTALL POND OUTLET STRUCTURES AND  
LEVEL SPREADER. PLUG BOTTOM OPENING  
FOR USE AS TEMPORARY SEDIMENT BASIN.
- 2) INSTALL MINOR ROAD CROSSING IN ACCORDANCE  
WITH GENERAL ARAP PERMIT.
- 3) CLEAR REMAINDER OF PHASE 3 AREA.  
REMOVE TOPSOIL AND STOCKPILE FOR  
REDISTRIBUTION. SEED TOPSOIL PILES.
- 4) ROUGH GRADE ROADWAYS AND BUILDING PADS.
- 5) INSTALL STORM SEWER, PROVIDE INLET AND  
OUTLET PROTECTION.
- 6) INSTALL WATER AND SANITARY SEWER FACILITIES.
- 7) FINAL GRADE ROADWAYS AND INSTALL PAVEMENT  
AND CURBS.
- 8) AFTER ALL CONSTRUCTION IS COMPLETED, AND  
ALL AREAS ARE STABILIZED, CONVERT TEMPORARY  
SEDIMENT PONDS TO PERMANENT STORMWATER  
DETENTION BASINS.

| STORM DRAINAGE SUMMARY |           |         |       |           |         |        |       |                     |
|------------------------|-----------|---------|-------|-----------|---------|--------|-------|---------------------|
| FROM                   | ELEVATION |         |       | ELEVATION |         |        |       | DIAMETER / MATERIAL |
|                        | GRATE     | INVERT  | TO    | GRATE     | INVERT  | LENGTH | SLOPE |                     |
| HW-5                   | ---       | 1118.50 | OS-2  | 1123.00   | 1118.80 | 30     | 1.00% | 24" RCP             |
| HW-6                   | ---       | 1122.00 | WQ-1  | 1126.00   | 1122.50 | 16     | 3.13% | 18" RCP             |
| WQ-1                   | 1126.00   | 1122.50 | CB-16 | 1126.00   | 1123.00 | 40     | 1.25% | 18" HDPE            |
| CB-16                  | 1126.00   | 1123.00 | CB-17 | 1126.00   | 1123.30 | 26     | 1.15% | 18" HDPE            |
| WQ-1                   | 1126.00   | 1122.50 | CB-29 | 1130.00   | 1125.00 | 75     | 3.33% | 18" HDPE            |
| CB-29                  | 1130.00   | 1125.00 | AD-4  | 1130.00   | 1126.00 | 47     | 2.13% | 18" HDPE            |
|                        |           |         |       |           |         |        |       |                     |
| HW-7                   | ---       | 1118.50 | OS-3  | 1123.00   | 1118.80 | 30     | 1.00% | 18" RCP             |
| HW-8                   | ---       | 1120.00 | WQ-2  | 1126.00   | 1120.20 | 25     | 0.80% | 24" HDPE            |
| WQ-2                   | 1126.00   | 1120.20 | CB-18 | 1124.90   | 1120.80 | 102    | 0.59% | 18" HDPE            |
| CB-18                  | 1124.90   | 1120.80 | CB-19 | 1124.90   | 1121.30 | 26     | 1.92% | 18" HDPE            |
| CB-18                  | 1124.90   | 1120.80 | CB-20 | 1126.00   | 1122.30 | 109    | 1.38% | 18" HDPE            |
| CB-20                  | 1126.00   | 1122.30 | CB-21 | 1126.00   | 1122.60 | 26     | 1.15% | 18" HDPE            |

| STORM DRAINAGE SUMMARY |                    |                     |       |                    |                     |        |       |                        |  |
|------------------------|--------------------|---------------------|-------|--------------------|---------------------|--------|-------|------------------------|--|
| FROM                   | ELEVATION<br>GRATE | ELEVATION<br>INVERT | TO    | ELEVATION<br>GRATE | ELEVATION<br>INVERT | LENGTH | SLOPE | DIAMETER /<br>MATERIAL |  |
| HW-9                   | ---                | 1123.40             | OS-4  | 1129.80            | 1123.90             | 40     | 1.25% | 30" RCP                |  |
| HW-10                  | ---                | 1128.00             | WQ-3  | 1132.10            | 1128.20             | 14     | 1.43% | 24" HDPE               |  |
| WQ-3                   | 1132.10            | 1128.20             | CB-22 | 1132.00            | 1128.50             | 49     | 0.61% | 24" HDPE               |  |
| CB-22                  | 1132.00            | 1128.50             | CB-23 | 1132.00            | 1128.80             | 26     | 1.15% | 18" HDPE               |  |
| CB-22                  | 1132.00            | 1128.80             | CB-24 | 1138.20            | 1134.20             | 119    | 4.54% | 18" HDPE               |  |
| CB-24                  | 1138.30            | 1134.20             | CB-25 | 1138.20            | 1134.70             | 26     | 1.92% | 18" HDPE               |  |
| CB-24                  | 1138.30            | 1134.20             | CB-26 | 1154.50            | 1150.50             | 218    | 7.48% | 18" HDPE               |  |
| CB-26                  | 1154.50            | 1150.50             | CB-27 | 1158.20            | 1153.70             | 154    | 2.08% | 18" HDPE               |  |
| CB-27                  | 1158.20            | 1153.70             | CB-28 | 1158.20            | 1154.20             | 26     | 1.92% | 18" HDPE               |  |
| EW-1                   | ---                | 1116.92             | EW-2  | ---                | 1117.60             | 68     | 1.00% | BOX CULVERT            |  |

Standard Notes:

1. This is a priority construction activity.
2. Adequate drainage, erosion and sediment control measures, best management practices and/or other stormwater management facilities shall be provided and maintained at all times during construction. Damages to adjacent property and/or the construction site caused by the contractor's or property owner's failure to provide and maintain adequate drainage and erosion/sediment control for the construction area shall be the responsibility of the property owner and/or contractor.
3. Quality assurance of erosion prevention and sediment controls shall be conducted by qualified personnel performing site assessment at each outfall involving drainage totaling 10 or more acres, or five or more acres if draining to impaired or exceptional waters. This assessment will be conducted at each qualifying outfall within a month of construction commencement. (see CGP sec 3.1.2 for assessment language)
4. Fugitive sediment that has escaped the construction site must be removed so that it is not subsequently washed into storm sewers and/or streams by the next rain and/or so that it does not pose a safety hazard to users of public streets. Arrangements concerning removal of sediment on adjoining property must be settled by the permittee with the adjoining land owner.
5. Sediment should be removed from sediment traps, silt fences, sedimentation ponds, other sediment controls when design capacity has been reduced by 50%.
6. Litter, construction debris, and construction chemicals exposed to stormwater shall be picked up prior to anticipated storm events or before being carried off the site by wind, or otherwise prevented from becoming a pollution source for stormwater discharges.
7. Preconstruction vegetative ground cover shall not be destroyed, removed, or disturbed more than 15 days prior to grading or earth moving unless the area is seeded and/or mulched or other temporary cover is installed.
8. Existing vegetation should be preserved to the maximum extent practicable.
9. Temporary or permanent soil stabilization must be completed no later than 15 days after the construction activity in that portion of the site has permanently or temporarily ceased. Steep slopes (>35%) must be permanently or temporarily stabilized within 7 days.
10. Site inspections shall be performed at least twice weekly at a minimum of 72 hours apart on all unstabilized sites.

| NO.       | DATE | DESCRIPTION | BY | CHKD. |
|-----------|------|-------------|----|-------|
| REVISIONS |      |             |    |       |







ROBERT G. CAMPBELL & ASSOC., L.P.  
CONSULTING ENGINEERS  
KNOXVILLE, TENNESSEE

TWIN OAK LANDING  
STORMWATER POLLUTION PREVENTION PLAN

GRADING & DRAINAGE PLAN  
SWPPP PHASE 3

|                    |                   |                   |                                     |
|--------------------|-------------------|-------------------|-------------------------------------|
| DESIGNED BY<br>GMT | CHECKED BY<br>RGC | SCALE<br>1" = 60' | SHEET FOUR<br>NO. 4<br>OF 13 SHEETS |
| DRAWN BY<br>JER    | DATE<br>7-23-20   | FILE NO.<br>15041 |                                     |






**TYPICAL 2 LANE STREET PUBLIC ROADS**

BORROW MATERIALS TO BE USED FOR FILL SHALL BE TESTED FOR MAXIMUM DRY DENSITY AND OPTIMUM MOISTURE CONTENT (STANDARD PROCTOR ASTM D698) PRIOR TO PLACEMENT OF FILL.



FILL SOILS SHALL BE COMPACTED IN LAYERS 8 INCHES OR LESS IN THICKNESS TO A MINIMUM OF 98 PERCENT STANDARD PROCTOR MAXIMUM DRY DENSITY AND WITHIN PLUS OR MINUS 3 PERCENT OPTIMUM MOISTURE CONTENT. NO LESS THAN SIX (6) DENSITY TESTS SHALL BE PERFORMED IN EVERY 10,000 SQUARE FEET OF AREA PER 8 INCH LIFT. (APPROX. 1 TEST PER EVERY 50 SQ. FT.)

\* "D" MIX REQUIRED ON FINAL SURFACE WHERE GRADE IS 10% OR GREATER.


8-SA-20-C  
8-B-20-UR  
Revised: 7/23/2020







STANDARD DETAIL 6" EXTRUDED CURB




TYPICAL 2 LANE STREET  
PUBLIC ROADS

BORROW MATERIALS TO BE USED FOR FILL SHALL BE TESTED FOR MAXIMUM DRY DENSITY AND OPTIMUM MOISTURE CONTENT (STANDARD PROCTOR ASTM D698) PRIOR TO PLACEMENT OF FILL.



FILL SOILS SHALL BE COMPACTED IN LAYERS 8 INCHES OR LESS IN THICKNESS TO A MINIMUM OF 98 PERCENT STANDARD PROCTOR MAXIMUM DRY DENSITY AND WITHIN PLUS OR MINUS 3 PERCENT OPTIMUM MOISTURE CONTENT. NO LESS THAN SIX (6) DENSITY TESTS SHALL BE PERFORMED IN EVERY 10,000 SQUARE FEET OF AREA PER 8 INCH LIFT. (APPROX. 1 TEST PER EVERY 50 SQ. FT.)

\* "D" MIX REQUIRED ON FINAL SURFACE WHERE GRADE IS 10% OR GREATER.

8-SA-20-C  
8-B-20-UR  
Revised: 8/1/2020









TAZEWELL PIKE WIDENING DETAIL  
TDOT PAVEMENT SECTION  
NO SCALE

- TDOT STANDARD DRAWINGS TO BE REFERENCED:
- SIDEWALKS: RP-S-7
- CURB: RP-NMC-10
- CURB RAMPS: RP-H-3
- RP-H-4
- RP-H-5
- RP-H-8
- RP-H-9
- STRIPING: T-M-1
- T-M-2
- T-M-3
- T-M-4

- LEGEND
- EIP IRON PIN FOUND
  - PIPE • PIPE FOUND
  - G.V. GAS VALVE
  - W.M. WATER METER
  - MANHOLE
  - ⊥ SIGN
  - W.V. WATER VALVE
  - ⊗ FIRE HYDRANT
  - P/T POWER/TELEPHONE
  - GUY WIRE
  - ⊕ SURVEY CONTROL POINT



- NOTES:
- 1) LEFT HAND TURN LANE TO BE PROVIDED FROM TAZEWELL PIKE ONTO TWIN OAK LANE.
  - 2) TWIN OAK LANE TO BE WIDENED TO 26 FEET WITH DITCH AND SIDEWALK EXTENDING TO TAZEWELL PIKE.
  - 3) EXISTING DECELERATION LANE TO GIBBS SCHOOLS TO BE EXTENDED WITH DRAINAGE DITCH AND SIDEWALK TO GIBBS SCHOOL PROPERTY.
  - 4) EXISTING 30" HDPE UNDER TAZEWELL PIKE TO BE EXTENDED WITH AREA DRAIN AND HEADWALL.
  - 5) OVERLAY EXISTING TAZEWELL PIKE WITH NEW 1" THICK ASPHALT SURFACE COAT IN ACCORDANCE WITH TDOT SPECIFICATIONS. NEW ASPHALT TO FOLLOW WITH CROSS SLOPE OF EXISTING ROAD.
  - 6) NEW STRIPING TO BE AS PER TDOT SPECIFICATIONS.
  - 7) OVERLAY EXISTING TWIN OAK LANE WITH NEW 1" THICK ASPHALT SURFACE COAT IN ACCORDANCE WITH KNOX COUNTY SPECIFICATIONS.
  - 8) DRAINAGE IMPROVEMENTS TO BE CONSTRUCTED IN ACCORDANCE WITH TDOT SPECIFICATIONS. SEE STANDARD DRAWINGS D-PB-2, D-JBS-1, & D-CB-38S.
  - 9) EXISTING ELEVATIONS BASED ON TOPOGRAPHIC SURVEY, NAVD 1988.
  - 10) EXISTING UTILITIES TO BE RELOCATED AS NEEDED. NO VALVES, BOXES, OR LIDS TO BE LOCATED IN SIDEWALKS.
  - 11) LOCATION OF EXISTING UNDERGROUND UTILITIES ARE APPROXIMATE BASED ON SURFACE FIXTURES AND OTHER AVAILABLE INFORMATION. THERE MAY BE OTHER UNDERGROUND UTILITIES NOT SHOWN. PRIOR TO EXCAVATION, A TN ONE-CALL SHOULD BE MADE TO REQUEST UTILITY MARKING.
  - 12) CONTRACTOR TO WORK DURING OFF PEAK TIMES WHILE IN THE RIGHT OF WAY
  - 13) RELOCATED UTILITY POLES TO BE 10' OFF CURB
  - 14) MILL ASPHALT AT TIE INS FOR A SMOOTH TRANSITION
  - 15) RELOCATE SCHOOL FLASHERS AND SCHOOL ZONE SIGNS



8-SA-20-C  
8-B-20-UR  
Revised: 7/23/2020

|     |      |             |  |    |      |   |  |   |  |                 |  |                    |                   |                   |  |
|-----|------|-------------|--|----|------|---|--|---|--|-----------------|--|--------------------|-------------------|-------------------|--|
|     |      |             |  |    |      | ROBERT G. CAMPBELL & ASSOC., L.P.<br>CONSULTING ENGINEERS<br>KNOXVILLE, TENNESSEE |  | TWIN OAK LANDING<br>TAZEWELL PIKE (S.R. 331) - WIDENING & STRIPING PLAN |  | PROPOSED LAYOUT |  | DESIGNED BY<br>GMT | CHECKED BY<br>RGC | SCALE<br>AS SHOWN | SHEET<br>NO. <b>2</b><br>OF SIX SHEETS |
| NO. | DATE | DESCRIPTION |  | BY | CKD. |   |  |   |  |                 |  | DRAWN BY<br>GMT    | 8-10-18           | FILE NO.<br>15041 |  |