



Catalog Number
Notes
Type

9-A-21-UR
8/23/2021

Contractor Select™

TWX LED ALO

Adjustable Light Output Wall Pack



TWX LED wall pack family is a ground design that has the low initial cost customers demand while providing superior performance and a traditional form. The Adjustable Light Output (ALO) feature allows the contractor to set the light output during installation, to a level perfectly suited for the job site.

FEATURES:

- Replaces 70W to 400W HID luminaires, providing up to 83% in energy savings.
- Same footprint as a standard HID wall pack, to easily cover the stain
- Expected service life of more than 20 years.
- Vandal-resistant polycarbonate lens option.



Catalog Number	UPC	Description	Replaces Up To	Lumens	Wattage	Photocell	CCT	Voltage	Finish	Pallet qty.
TWX1 LED P2 40K MVOLT PE DDBTXD	194995034444	Wall Packs	CFL - 100W Metal Halide	2,950	22W	Yes	4000K	120-277V	TEXTURED DARK BRONZE	98
TWX1 LED ALO 40K MVOLT DDBTXD	194994620464	Wall Packs	CFL - 100W Metal Halide	600 - 2,950	22W	No	4000K	120-277V	TEXTURED DARK BRONZE	98
TWX1 LED ALO 50K MVOLT DDBTXD	194994620457	Wall Packs	CFL - 100W Metal Halide	600 - 2,950	22W	No	5000K	120-277V	TEXTURED DARK BRONZE	98
TWX2 LED ALO 40K MVOLT DDBTXD	194994620488	Wall Packs	70W - 250W Metal Halide	1,450 - 6,950	54W	No	4000K	120-277V	TEXTURED DARK BRONZE	77
TWX2 LED ALO 50K MVOLT DDBTXD	194994620495	Wall Packs	70W - 250W Metal Halide	1,450 - 6,950	54W	No	5000K	120-277V	TEXTURED DARK BRONZE	77
TWX3 LED ALO 40K MVOLT DDBTXD	194994620594	Wall Packs	100W - 400W Metal Halide	2,900 - 13,850	108W	No	4000K	120-277V	TEXTURED DARK BRONZE	42
TWX3 LED ALO 50K MVOLT DDBTXD	194994620549	Wall Packs	100W - 400W Metal Halide	2,900 - 13,850	108W	No	5000K	120-277V	TEXTURED DARK BRONZE	42
TWPX3 LED ALO 50K MVOLT DDBTXD (Polycarbonate Lens)	194994620556	Wall Packs	100W - 400W Metal Halide	2,750 - 13,200	108W	No	5000K	120-277V	TEXTURED DARK BRONZE	42

More configurations are available. [Click here](#) or visit www.acuitybrands.com and search for TWX LED.



9-A-21-UR
8/23/2021

Specifications

INTENDED USE:

The TWX LED is an energy-efficient, low maintenance LED wall pack family for replacing 70W to 400W HID luminaires, providing the same footprint on the wall. TWX is ideal for applications such as carports, loading areas, storage units, warehouses and parking areas.

CONSTRUCTION:

Two-piece die-cast aluminum housing to optimize thermal management through conductive and convective cooling. The door is hinged on the side and can be removed for easy installation. The housing is completely sealed against moisture and environmental contaminants (IP65) and is suitable for the hose-down applications.

FINISH:

Exterior painted parts are protected by a zinc-infused Super Durable TGIC thermoset powder coat finish that provides superior resistance to corrosion and weathering. A tightly controlled multi-stage process ensures a 3 mils thickness for a finish that can withstand extreme climate changes without cracking or peeling.

OPTICS:

The advanced optical design uses both reflector and refractor technologies that work together to create superior illumination and further throw, getting the light where it is needed. The US-made borosilicate glass refractor is specifically designed to maximize light extraction and create a fully luminous luminaire for a better nighttime look. On TWPX models, the UV stabilized polycarbonate lens provides vandal resistance along with superior light distribution.

ELECTRICAL:

Light engine consists of high-efficacy LEDs mounted to housing to maximize heat dissipation and promote long-life (up to L81/100,000 hours at 25°C). The electronic driver has a power factor of >90%, THD <20%. Luminaire is 0-10V dimmable.

INSTALLATION:

Designed for wall mounting above four feet from the ground. Housing is configured for mounting directly over a standard junction box (by others) or for surface wiring via any of 1/2" threaded entry hubs.

LISTINGS:

CSA certified to U.S. and Canadian standards. IP65 rated for outdoor applications. Rated for -40°C minimum ambient.

DesignLights Consortium® (DLC) qualified product. Not all versions of this product may be DLC qualified. Please check the DLC Qualified Products List at www.designlights.org/QPL to confirm which versions are qualified.

WARRANTY:

5-year limited warranty. Complete warranty terms located at:

www.acuitybrands.com/support/customer-support/terms-and-conditions

Note: Actual performance may differ as a result of end-user environment and application.

All values are design or typical values, measured under laboratory conditions at 25 °C.

Specifications subject to change without notice.

Dimensions


TWX1:

Width: 7.5"

Height: 12.0"

Depth: 5.0"

Weight: 9 lbs




TWX2:

Width: 13.0"

Height: 9.0"

Depth: 4.5"

Weight: 11 lbs



TWX3/TWPX3:

Width: 18.0"

Height: 14.0"


Depth: 5.0"

21 lbs

(Glass)

Weight: 13 lbs

(Polycarbonate)






RSX2 LED Area Luminaire



9-A-21-UR
8/23/2021

Specifications

EPA (ft ² @0°):	0.69 ft ² (0.06 m ²)
Length:	29.3" (74.4 cm) (SPA mount)
Width:	13.4" (34.0 cm)
Height:	3.0" (7.6 cm) Main Body 7.2" (18.3 cm) Arm
Weight: (SPA mount)	30.0 lbs (13.6 kg)



Catalog
Number

Notes

Type

Hit the Tab key or mouse over the page to see all interactive elements.

Introduction

The new RSX LED Area family delivers maximum value by providing significant energy savings, long life and outstanding photometric performance at an affordable price. The RSX2 delivers 11,000 to 31,000 lumens allowing it to replace 250W to 1000W HID luminaires.

The RSX features an integral universal mounting mechanism that allows the luminaire to be mounted on most existing drill hole patterns. This "no-drill" solution provides significant labor savings. An easy-access door on the bottom of mounting arm allows for wiring without opening the electrical compartment. A mast arm adaptor, adjustable integral slipfitter and other mounting configurations are available.

Ordering Information

EXAMPLE: RSX2 LED P6 40K R3 MVOLT SPA DDBXD

RSX2 LED					
Series	Performance Package	Color Temperature	Distribution	Voltage	Mounting
RSX2 LED	P1	30K 3000K	R2 Type 2 Wide	MVOLT (120V-277V) ²	SPA Square pole mounting (3.0" min. SQ pole for 1 at 90°, 3.5" min. SQ pole for 2, 3, 4 at 90°)
	P2	40K 4000K	R3 Type 3 Wide	HVOLT (347V-480V) ³	RPA Round pole mounting (3.2" min. dia. RND pole for 2, 3, 4 at 90°, 3.0" min. dia. RND pole for 1 at 90°, 2 at 180°, 3 at 120°)
	P3	50K 5000K	R3S Type 3 Short	XVOLT (277V-480V) ⁴	MA Mast arm adaptor (fits 2-3/8" OD horizontal tenon)
	P4		R4 Type 4 Wide	(use specific voltage for options as noted)	IS Adjustable slipfitter (fits 2-3/8" OD tenon) ⁶
	P5		R4S Type 4 Short	120 ³ 277 ⁵	WBA Wall bracket ¹
	P6		R5 Type 5 Wide ¹	208 ³ 347 ⁵	WBASC Wall bracket with surface conduit box
			R5S Type 5 Short ¹	240 ³ 480 ⁵	AASP Adjustable tilt arm square pole mounting ⁶
			AFR Automotive Front Row		AARP Adjustable tilt arm round pole mounting ⁶
			AFRR90 Automotive Front Row Right Rotated		AAWB Adjustable tilt arm with wall bracket ⁶
			AFRL90 Automotive Front Row Left Rotated		AAWSC Adjustable tilt arm wall bracket and surface conduit box ⁶

Options			Finish
Shipped Installed HS House-side shield ⁷ PE Photocontrol, button style ^{8,9} PEX Photocontrol external threaded, adjustable ^{9,10} PER7 Seven-wire twist-lock receptacle only (no controls) ^{9,11,12,13} CE34 Conduit entry 3/4" NPT (Qty 2) SF Single fuse (120, 277, 347) ⁵ DF Double fuse (208, 240, 480) ⁵ SPD20KV 20KV Surge pack (10KV standard) FAO Field adjustable output ^{9,13} DMG 0-10V dimming extend out back of housing for external control (control ordered separate) ^{9,13} DS Dual switching ^{9,14}			DDBXD Dark Bronze DBLXD Black DNAXD Natural Aluminum DWHXD White DDBTXD Textured Dark Bronze DBLBXD Textured Black DNATXD Textured Natural Aluminum DWHGXD Textured White
Shipped Installed *Standalone and Networked Sensors/Controls (factory default settings, see table page 9) NLTAIR2 nLight AIR generation 2 ^{13,15,16} PIRHN Networked, Bi-Level motion/ambient sensor (for use with NLTAIR2) ^{13,16,17} BAA Buy America(n) Act Compliant *Note: PIRHN with nLight Air can be used as a standalone dimming sensor with out-of-box settings or as a wireless networked solution. See factory default settings table. Sensor coverage pattern is affected when luminaire is tilted. Shipped Separately (requires some field assembly) EGS External glare shield ⁶ EGFV External glare full visor (360° around light aperture) ⁷ BS Bird spikes ¹⁸			



Ordering Information

Accessories

Ordered and shipped separately.


RSX2HS	RSX2 House side shield (includes 2 shields)
RSX2EGS (FINISH) U	External glare shield (specify finish)
RSX2HSAFRR (FINISH) U	RSX2 House side shields for AFR rotated optics (includes 2 shields)
RSX2EGFV (FINISH) U	External glare full visor (specify finish)
RSXRPA (FINISH) U	RSX Universal round pole adaptor plate (specify finish)
RSXWBA (FINISH) U	RSX WBA wall bracket (specify finish) ¹
RSXSCB (FINISH) U	RSX Surface conduit box (specify finish, for use with WBA, WBA not included)
DLL127F 1.5 JU	Photocell -SSL twist-lock (120-277V) ¹⁹
DLL347F 1.5 CUL JU	Photocell -SSL twist-lock (347V) ¹⁹
DLL480F 1.5 CUL JU	Photocell -SSL twist-lock (480V) ¹⁹
DSHORT SBK U	Shorting cap ¹⁹

NOTES

- Any Type 5 distribution, is not available with WBA.
- MVOLT driver operates on any line voltage from 120-277V (50/60 Hz).
- HVOLT driver operates on any line voltage from 347-480V (50/60 Hz).
- XVOLT driver not available with P1. XVOLT driver operates on any line voltage from 277V-480V (50/60 Hz). XVOLT not available with fusing (SF or DF) and not available with PE or PEX.
- Single fuse (SF) requires 120V, 277V or 347V. Double fuse (DF) requires 208V, 240V or 480V.
- Maximum tilt is 90° above horizontal.
- It may be ordered as an accessory.
- Requires MVOLT or 347V.
- Not available in combination with other light sensing control options (following options cannot be combined: PE, PEX, PER7, FAO, DMG, DS, PIRHN).
- Requires 120V, 208V, 240V, or 277V.

- Twistlock photocell ordered and shipped as a separate line item from Acuity Brands Controls. See accessories. Shorting Cap included. Dimming leads capped for future use.
- For units with option PER7, the mounting must be restricted to +/- 45° from horizontal aim per ANSI C136.10-2010.
- Two or more of the following options cannot be combined including DMG, DS, PER7, FAO and PIRHN.
- DS only available on performance package P5 and P6.
- Must be ordered with PIRHN.
- Requires MVOLT or HVOLT.
- Must be ordered with NLTAIR2. For additional information on PIRHN visit [here](#).
- Must be ordered with fixture for factory pre-drilling.
- Requires luminaire to be specified with PER7 option. Ordered and shipped as a separate line item from Acuity Brands Controls.

External Shields



House Side Shield



External Glare Shield




External 360 Full Visor


Pole/Mounting Information

Accessories including bullhorns, cross arms and other adapters are available under the accessories tab at Lithonia's Outdoor Poles and Arms product page. Click here to visit [Accessories](#).


HANDHOLE ORIENTATION



RSX POLE DRILLING



RSX STANDARD ARM & ADJUSTABLE ARM



Round Tenon Mount - Pole Top Slipfitters










Tenon O.D.	RSX Mounting	Single	2 at 180°	2 at 90°	3 at 120°	3 at 90°	4 at 90°
2 - 3/8"	RPA, AARP	AS3-5 190	AS3-5 280	AS3-5 290	AS3-5 320	AS3-5 390	AS3-5 490
2 - 7/8"	RPA, AARP	AST25-190	AST25-280	AST25-290	AST25-320	AST25-390	AST25-490
4"	RPA, AARP	AST35-190	AST35-280	AST35-290	AST35-320	AST35-390	AST35-490

Drill/Side Location by Configuration Type

Drilling Template	Mounting Option	Single	2 @ 180	2 @ 90	3 @ 120	3 @ 90	4 @ 90
	Head Location	Side B	Side B & D	Side B & C	Round Pole Only	Side B, C & D	Side A, B, C & D
#8	Drill Nomenclature	DM19AS	DM28AS	DM29AS	DM32AS	DM39AS	DM49AS

RSX2 - Luminaire EPA


*Includes luminaire and integral mounting arm. Other tenons, arms, brackets or other accessories are not included in this EPA data.

Fixture Quantity & Mounting Configuration		Single	2 @ 90	2 @ 180	3 @ 90	3 @ 120	4 @ 90	2 Side by Side	3 Side by Side	4 Side by Side
Mounting Type	Tilt									
SPA - Square Pole Adaptor	0 °	0.69	1.22	1.27	1.8	1.61	2.39	1.37	2.06	2.74
RPA - Round Pole Adaptor		0.74	1.27	1.37	1.9	1.71	2.49	1.42	2.16	2.84
MA - Mast Arm Adaptor		0.61	1.14	1.11	1.64	1.45	2.23	1.29	1.9	2.58
IS - Integral Slipfitter AASP/AARP - Adjustable Arm Square/Round Pole	0 °	0.69	1.22	1.27	1.8	1.61	2.39	1.37	2.06	2.74
	10°	0.53	1.06	1.05	1.58	1.37	2.08	1.06	1.59	2.12
	20°	0.52	1.02	1.03	1.52	1.33	2.02	1.03	1.55	2.07
	30°	0.64	1.11	1.18	1.63	1.45	2.21	1.27	1.91	2.54
	40°	0.81	1.21	1.35	1.74	1.65	2.39	1.62	2.43	3.23
	45°	0.91	1.25	1.5	1.81	1.75	2.48	1.82	2.73	3.64
	50°	1.34	1.83	2.17	2.61	2.56	3.62	2.68	4.02	5.36
	60°	2.2	2.97	3.57	4.24	4.17	5.89	4.41	6.61	8.82
	70°	2.86	4.13	4.7	5.89	5.71	8.21	5.71	8.57	11.42
	80°	3.4	5.13	5.67	7.34	7.09	10.21	6.79	10.19	13.59
90°	3.85	5.96	6.55	8.58	8.31	11.88	7.70	11.56	15.41	

Photometric Diagrams

To see complete photometric reports or download .ies files for this product, visit Lithonia Lighting's RSX Area homepage.

Isofootcandle plots for the RSX2 LED P6 40K. Distances are in units of mounting height (30').



Performance Data

Lumen Ambient Temperature (LAT) Multipliers

Use these factors to determine relative lumen output for average ambient temperatures from 0-50°C (32-122°F).

Ambient	Ambient	Lumen Multiplier
0°C	32°F	1.05
5°C	41°F	1.04
10°C	50°F	1.03
15°C	59°F	1.02
20°C	68°F	1.01
25°C	77°F	1.00
30°C	86°F	0.99
35°C	95°F	0.98
40°C	104°F	0.97
45°C	113°F	0.96
50°C	122°F	0.95

Electrical Load

Performance Package	System Watts (W)	Current (A)					
		120V	208V	240V	277V	347V	480V
P1	71W	0.59	0.34	0.30	0.26	0.20	0.15
P2	111W	0.93	0.53	0.46	0.40	0.32	0.23
P3	147W	1.23	0.70	0.61	0.53	0.42	0.31
P4	187W	1.55	0.90	0.78	0.68	0.53	0.38
P5	210W	1.75	1.01	0.87	0.76	0.60	0.44
P6	244W	2.03	1.17	1.01	0.88	0.70	0.51

Projected LED Lumen Maintenance

Operating Hours	50,000	75,000	100,000
Lumen Maintenance Factor	>0.97	>0.95	>0.92

Values calculated according to IESNA TM-21-11 methodology and valid up to 40°C.

Performance Data

Lumen Output

Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of the configurations shown, within the tolerances allowed by Lighting Facts. Contact factory for performance data on any configurations not shown here.


Performance Package	System Watts	Distribution. Type	30K (3000K, 70 CRI)					40K (4000K, 70 CRI)					50K (5000K, 70 CRI)				
			Lumens	B	U	G	LPW	Lumens	B	U	G	LPW	Lumens	B	U	G	LPW
P1	71W	R2	10,040	2	0	1	139	11,031	2	0	1	153	11,031	2	0	1	153
		R3	10,005	2	0	2	141	10,992	2	0	2	155	10,992	2	0	2	155
		R3S	10,271	2	0	2	143	11,285	2	0	2	157	11,285	2	0	2	157
		R4	10,136	2	0	2	143	11,136	2	0	2	157	11,136	2	0	2	157
		R4S	9,779	2	0	2	138	10,744	2	0	2	151	10,744	2	0	2	151
		R5	10,271	4	0	2	145	11,285	4	0	2	159	11,285	4	0	2	159
		R5S	10,544	3	0	1	149	11,585	3	0	2	163	11,585	3	0	2	163
		AFR	10,026	2	0	1	141	11,016	2	0	1	155	11,016	2	0	1	155
		AFRR90	10,122	3	0	2	140	11,121	3	0	2	154	11,121	3	0	2	154
		AFRL90	10,164	3	0	2	141	11,167	3	0	2	155	11,167	3	0	2	155
P2	111W	R2	15,712	2	0	2	138	17,263	2	0	2	151	17,263	2	0	2	151
		R3	15,657	2	0	3	141	17,202	3	0	3	155	17,202	3	0	3	155
		R3S	16,075	2	0	2	141	17,661	2	0	2	155	17,661	2	0	2	155
		R4	15,862	2	0	3	143	17,427	2	0	3	157	17,427	2	0	3	157
		R4S	15,304	2	0	2	138	16,815	2	0	2	151	16,815	2	0	2	151
		R5	16,075	4	0	2	145	17,661	5	0	3	159	17,661	5	0	3	159
		R5S	16,502	4	0	2	149	18,130	4	0	2	163	18,130	4	0	2	163
		AFR	15,691	2	0	2	141	17,240	2	0	2	155	17,240	2	0	2	155
		AFRR90	15,841	3	0	3	139	17,404	4	0	3	153	17,404	4	0	3	153
		AFRL90	15,907	3	0	3	139	17,477	4	0	3	153	17,477	4	0	3	153
P3	147W	R2	19,855	3	0	2	132	21,814	3	0	2	145	21,814	3	0	2	145
		R3	19,785	3	0	3	135	21,737	3	0	4	148	21,737	3	0	4	148
		R3S	20,312	3	0	3	135	22,317	3	0	3	149	22,317	3	0	3	149
		R4	20,044	3	0	3	136	22,022	3	0	4	150	22,022	3	0	4	150
		R4S	19,339	3	0	3	132	21,247	3	0	3	145	21,247	3	0	3	145
		R5	20,313	5	0	3	138	22,317	5	0	3	152	22,317	5	0	3	152
		R5S	20,852	4	0	2	142	22,910	4	0	2	156	22,910	4	0	2	156
		AFR	19,828	3	0	2	135	21,785	3	0	2	148	21,785	3	0	2	148
		AFRR90	20,017	4	0	3	133	21,992	4	0	3	147	21,992	4	0	3	147
		AFRL90	20,101	4	0	3	134	22,084	4	0	3	147	22,084	4	0	3	147
P4	187W	R2	22,836	3	0	2	120	25,090	3	0	2	132	25,090	3	0	2	132
		R3	22,756	3	0	4	122	25,002	3	0	4	134	25,002	3	0	4	134
		R3S	23,363	3	0	3	123	25,668	3	0	3	135	25,668	3	0	3	135
		R4	23,054	3	0	4	123	25,329	3	0	4	135	25,329	3	0	4	135
		R4S	22,243	3	0	3	119	25,059	3	0	3	134	25,059	3	0	3	134
		R5	23,363	5	0	3	125	25,669	5	0	4	137	25,669	5	0	4	137
		R5S	23,983	4	0	2	128	26,350	4	0	2	141	26,350	4	0	2	141
		AFR	22,806	3	0	2	122	25,056	3	0	2	134	25,056	3	0	2	134
		AFRR90	23,023	4	0	3	121	25,295	4	0	3	133	25,295	4	0	3	133
		AFRL90	23,120	4	0	3	122	25,401	4	0	3	134	25,401	4	0	3	134
P5	210W	R2	26,141	3	0	2	122	28,721	3	0	2	135	28,721	3	0	2	135
		R3	26,049	3	0	4	124	28,620	3	0	4	136	28,620	3	0	4	136
		R3S	26,744	3	0	3	125	29,383	3	0	4	138	29,383	3	0	4	138
		R4	26,390	3	0	4	126	28,994	3	0	4	138	28,994	3	0	4	138
		R4S	25,462	3	0	3	121	27,974	3	0	3	133	27,974	3	0	3	133
		R5	26,744	5	0	4	127	29,383	5	0	4	140	29,383	5	0	4	140
		R5S	27,454	4	0	2	131	30,163	4	0	2	144	30,163	4	0	2	144
		AFR	26,106	3	0	2	124	28,682	3	0	2	137	28,682	3	0	2	137
		AFRR90	26,354	4	0	3	123	28,955	5	0	3	136	28,955	5	0	3	136
		AFRL90	26,465	4	0	3	124	29,077	5	0	3	136	29,077	5	0	3	136
P6	244W	R2	27,646	3	0	2	112	30,374	3	0	2	123	30,374	3	0	2	123
		R3	27,549	3	0	4	113	30,267	3	0	4	124	30,267	3	0	4	124
		R3S	28,283	3	0	3	115	31,075	3	0	4	126	31,075	3	0	4	126
		R4	27,909	3	0	4	114	30,663	3	0	4	126	30,663	3	0	4	126
		R4S	26,928	3	0	3	110	29,585	3	0	3	121	29,585	3	0	3	121
		R5	28,284	5	0	4	116	31,075	5	0	4	127	31,075	5	0	4	127
		R5S	29,035	4	0	2	119	31,900	5	0	3	131	31,900	5	0	3	131
		AFR	27,608	3	0	2	112	30,332	3	0	2	123	30,332	3	0	2	123
		AFRR90	27,872	4	0	3	113	30,622	5	0	3	124	30,622	5	0	3	124
		AFRL90	27,989	4	0	3	113	30,751	5	0	3	125	30,751	5	0	3	125

Dimensions & Weights



Luminaire Weight by Mounting Type

Mounting Configuration	Total Luminaire Weight
SPA	30 lbs
RPA	32 lbs
MA	30 lbs
WBA	33 lbs
WBASC	36 lbs
IS	33 lbs
AASP	33 lbs
AARP	35 lbs
AAWB	36 lbs
AAWSC	39 lbs

RSX2 with Round Pole Adapter (RPA)




Length: 30.3" (77.0 cm)
 Width: 13.4" (34.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 7.2" (18.3 cm) Arm



Note: RPA — Round Pole mount can also be used to mount on square poles by omitting the round pole adapter plate shown here.



RSX2 with Mast Arm Adapter (MA)




Length: 30.6" (77.7 cm)
 Width: 13.4" (34.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 3.5" (8.9 cm) Arm




7/16" locking thru bolt/nut provided




RSX2 with Adjustable Slipfitter (IS)



Length: 28.3" (71.9 cm)
 Width: 13.4" (34.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 7.6" (19.3 cm) Arm






7/8" KO - fits 1/2" NPT water-tight fitting




Dimensions

RSX2 with Wall Bracket (WBA)






Length: 31.2" (79.2 cm)
 Width: 13.4" (41.7 cm)
 Height: 3.0" (7.6 cm) Main Body
 8.9" (22.6 cm) Arm

Wall Bracket (WBA) Mounting Detail




RSX2 with Wall Bracket with Surface Conduit Box (WBASC)



3/4" NPT taps with plugs - Qty (4) provided




Length: 32.8" (83.3 cm)
 Width: 13.4" (41.7 cm)
 Height: 3.0" (7.6 cm) Main Body
 9.2" (23.4 cm) Arm

Surface Conduit Box (SCB) Mounting Detail




Dimensions

RSX2 with Adjustable Tilt Arm - Square or Round Pole (AASP or AARP)



Length: 32.8" (83.3 cm) **AASP**
 33.8" (85.9 cm) **AARP**
 Width: 13.4" (34.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 7.2" (18.2 cm) Arm






NOTE:
 RPA - Round Pole mount can also be used to mount on square poles by omitting the round pole adapter plate shown here.

Notes


AASP: Requires 3.0" min. square pole for 1 at 90°. Requires 3.5" min. square pole for mounting 2, 3, 4 at 90°.

AARP: Requires 3.2" min. dia. round pole for 2, 3, 4 at 90°. Requires 3.0" min. dia. round pole for mounting 1 at 90°, 2 at 180°, 3 at 120°.


RSX2 with Adjustable Tilt Arm with Wall Bracket (AAWB)



Length: 34.7" (88.0 cm)
 Width: 13.4" (34.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 8.9" (22.6 cm) Arm







Wall Bracket (WBA) Mounting Detail




Dimensions

RSX2 with Adjustable Tilt Arm with Wall Bracket and Surface Conduit Box (AAWSC)




Length: 36.2" (91.9 cm)
 Width: 13.4" (40.0 cm)
 Height: 3.0" (7.6 cm) Main Body
 9.2" (23.4 cm) Arm


Surface Conduit Box (SCB) Mounting Detail



Additional Reference Drawings






Automotive Front Row - Rotated Optics (AFRL90/R90)



(Example: 2@180 - arrows indicate direction of light exiting the luminaire)

NLTAIR2 PIRHN nLight Sensor Coverage Pattern nLight PIRHN



Motion Sensor Default Settings - Option PIRHN						
Option	Dimmed State (unoccupied)	High Level (when occupied)	Photocell Operation	Dwell Time (occupancy time delay)	Ramp-up Time (from unoccupied to occupied)	Ramp-down Time (from occupied to unoccupied)
NLTAIR2 PIRHN	Approx. 30% Output	100% Output	Enabled @ 1.5FC	7.5 minutes	3 seconds	5 minutes

*Note: NLTAIR2 PIRHN default settings including photocell set-point, high/low dim rates, and occupancy sensor time delay are all configurable using the Clairity Pro App. Sensor coverage pattern shown with luminaire at 0°. Sensor coverage pattern is affected when luminaire is tilted.

FEATURES & SPECIFICATIONS

INTENDED USE

The RSX LED area luminaire is designed to provide a long-lasting, energy-efficient solution for the one-for-one replacement of existing metal halide or high pressure sodium lighting. The RSX2 delivers 11,000 to 31,000 lumens and is ideal for replacing 250W to 1000W HID pole-mounted luminaires in parking lots and other area lighting applications.

CONSTRUCTION AND DESIGN

The RSX LED area luminaire features a rugged die-cast aluminum main body that uses heat-dissipating fins and flow-through venting to provide optimal thermal management that both enhances LED performance and extends component life. Integral "no drill" mounting arm allows the luminaire to be mounted on existing pole drillings, greatly reducing installation labor. The light engines and housing are sealed against moisture and environmental contaminants to IP66. The low-profile design results in a low EPA, allowing pole optimization. Vibration rated per ANSI C136.31: 3G Mountings: Include SPA, RPA, MA, IS, AASP, AARP rated for 3G vibration. 1.5G Mountings: Include WBA, WBASC, AAWB and AAWSC rated for 1.5G vibration.

FINISH

Exterior parts are protected by a zinc-infused Super Durable TGIC thermoset powder coat finish that provides superior resistance to corrosion and weathering. A tightly controlled multi-stage process ensures superior adhesion as well as a minimum finish thickness of 3 mils. The result is a high-quality finish that is warrantied not to crack or peel.

OPTICS

Precision acrylic refractive lenses are engineered for superior application efficiency, distributing the light to where it is needed most. Available in short and wide pattern distributions including Type 2, Type 3, Type 3S, Type 4, Type 4S, Type 5, Type 5S, AFR (Automotive Front Row) and AFR rotated AFR90 and ARFL90.

ELECTRICAL

Light engine(s) configurations consist of high-efficacy LEDs mounted on metal-core circuit boards and aluminum heat sinks to maximize heat dissipation. Light engines are IP66 rated. LED lumen maintenance is >L92/100,000 hours. CCT's of 3000K, 4000K and 5000K (minimum 70 CRI) are available. Class 1 electronic drivers ensure system power factor >90% and THD <20%. Easily serviceable 10kV surge protection device meets a minimum Category C Low operation (per ANSI/IEEE C62.41.2).

STANDARD CONTROLS

The RSX LED area luminaire has a wide assortment of control options. Dusk to dawn controls include MVOLT and 347V button-type photocells and NEMA twist-lock photocell receptacles.

nLIGHT AIR CONTROLS

The RSX LED area luminaire is also available with nLight® AIR for the ultimate in wireless control. This powerful controls platform provides out-of-the-box basic motion sensing with photocontrol functionality and is suitable for mounting heights up to 40 feet. No commissioning is required when using factory default settings that provide basic stand-alone motion occupancy dimming that is switched on and off with a built-in photocell. See chart above for motion sensor default out-of-box settings. For more advanced wireless functionality, such as group dimming, nLight AIR can be commissioned using a smartphone and the easy-to-use CLAIRITY app. nLight AIR equipped luminaires can be grouped, resulting in motion sensor and photocell group response without the need for additional equipment. Scheduled dimming with motion sensor over-ride can be achieved when used with the nLight Eclipse. Additional information about nLight Air can be found [here](#).

INSTALLATION

Integral "no-drill" mounting arm allows for fast, easy mounting using existing pole drillings. Select the "SPA" option for square poles and the "RPA" option to mount to round poles. Note, the RPA mount can also be used for mounting to square poles by omitting the RPA adapter plate. Select the "MA" option to attach the luminaire to a 2 3/8" horizontal mast arm or the "IS" option for an adjustable slipfitter that mounts on a 2 3/8" OD tenon. The adjustable slipfitter has an integral junction box and offers easy installation. Can be tilted up to 90° above horizontal. Additional mountings are available including a wall bracket, adjustable tilt arm for direct-to-pole and wall and a surface conduit box for wall mount applications.

LISTINGS

CSA Certified to meet U.S. and Canadian standards. Suitable for wet locations. Rated for -40°C minimum ambient. DesignLights Consortium® (DLC) Premium qualified product and DLC qualified product. Not all versions of this product may be DLC Premium qualified or DLC qualified. Please check the DLC Qualified Products List at www.designlights.org/QPL to confirm which versions are qualified.

International Dark-Sky Association (IDA) Fixture Seal of Approval (FSA) is available for all products on this page utilizing 3000K color temperature only.



BUY AMERICAN

Product with the BAA option is assembled in the USA and meets the Buy America(n) government procurement requirements under FAR, DFARS and DOT. Please refer to www.acuitybrands.com/buy-american for additional information.

WARRANTY

5-year limited warranty. Complete warranty terms located at: www.acuitybrands.com/support/customer-support/terms-and-conditions

Note: Actual performance may differ as a result of end-user environment and application. All values are design or typical values, measured under laboratory conditions at 25 °C. Specifications subject to change without notice.



OVERALL SITE PLAN
SCALE: 1" = 100'-0"

PROJECT INFORMATION:

ADDRESS: 1946-1500 HARRIS RD
KNOXVILLE, TN 37924
060 011

PARCEL ID: 060 011

AUTHORITY HAVING JURISDICTION:
KNOX COUNTY

ZONING: PC-K PLANNED COMMERCIAL

SETBACKS:
PERIPHERY BORDER: 50'-0"

EASEMENT:
TYA TRANSMISSION 150'-0"

SITE INFORMATION:
TOTAL ACREAGE: 3.33 ACRES

PROPOSED USE:
NEW OFFICE & MAINTENANCE SHOP

BUILDING INFORMATION:
BUILDING SQUARE FOOTAGE: 7500 SF
BUILDING HEIGHT: 20'-4"
STORIES: 1 STORY + MEZZ.

PARKING INFORMATION:
PER 3,501.0 OFF STREET PARKING:
INDUSTRIAL AREAS
-ONE (1) PER TWO (2) EMPLOYEES ON THE COMBINED TWO (2) LARGEST SUCCESSIVE SHIFTS, PLUS ADEQUATE PARKING SPACE FOR CUSTOMER AND VISITOR VEHICLES AS DETERMINED BY THE PLANNING COMMISSION.

PROPOSED COMBINED TWO (2) LARGEST SUCCESSIVE SHIFTS: 10 WORKERS / 2 = 5 PARKING SPACES

PROPOSED CUSTOMER AND VISITOR VEHICLES: 6 PARKING SPACES

PROPOSED TOTAL PARKING: 11 PARKING.

PROPOSED TRAFFIC IMPACT STUDY NOT REQUIRED
LESS THAN 20 VEHICULAR VISITS A DAY.



BRABSTON TO HOUSE A MINIMUM OF (4) DUMP TRUCKS & (2) LOW BOY TRAILERS. VEHICLES TO LEAVE PROPERTY IN THE MORNING AND RETURN IN THE AFTERNOON. ADDITIONAL EQUIPMENT WILL BE BROUGHT TO THE PROPERTY FOR SERVICE AND STORAGE.

TREE LEGEND		
SYMBOL	TREE TYPE	QUANTITY
	FLOWERING DOGWOOD CORNUS FLORIDA MATURITY HEIGHT: LESS THAN 30 FT	3
	JAPANESE MAPLE ACER PALMATUM MATURITY HEIGHT: LESS THAN 30 FT	1
	AMERICAN BOXWOOD BUXUS SEMPERVIRENS MATURITY HEIGHT: LESS THAN 10 FT	20
	SASSAFRAS SASSAFRAS ALBIDUM MATURITY HEIGHT: 30 FT	25
	PERRINIAL FLOWERS VARIOUS	47
TOTAL		76

SIGNAGE CALCULATIONS			
SIGN	NEW / EXIST.	QUANTITY	SQ. FT.
MAIN ENTRY SIGN	NEW	1	50
BUILDING MOUNTED SIGN	NEW	1	45
TOTAL SIGNAGE QUANTITY AND SQ. FT. =		2	95

* PER KNOX COUNTY CODE OF ORDINANCES, APPENDIX A, ARTICLE 3.40.04
* PC, PLANNED COMMERCIAL ZONE BUSINESS GROUND SIGNS SHALL BE LIMITED TO ONE (1) PER EACH SEPARATE STREET FRONTAGE IN EXCESS OF ONE HUNDRED TWENTY-FIVE (125) FEET.

SITE LEGEND



SITE PLAN
SCALE: 1" = 40'-0"



File No.: 9-A-21-UR

Date submitted: 8/23/2021

These plans have not been reviewed by
Planning Staff and may not be finalized.



ARCHITECTURE, INC.

111 E. Jackson Avenue • Suite 101
Knoxville, Tennessee • 37915
phone: 865-546-9374 • fax: 865-673-9028
e-mail: design@dollar-ewers.com



NO.	REVISIONS
1	
2	
3	
4	
5	

KNOX COUNTY PLANNING NUMBER 9-A-21-UR


USE ON REVIEW REQUEST PACKAGE FOR
A NEW OFFICE WAREHOUSE
HARRIS RD, KNOXVILLE, TN
SCHEMATIC SITE PLAN

COPYRIGHT
ALL DRAWINGS, SPECIFICATIONS AND COPIES THEREOF
FURNISHED BY DOLLAR & EWERS ARCHITECTURE, INC.
ARE AND SHALL REMAIN THE PROPERTY OF DE&A, INC.
NO PART OF THIS PROJECT OR ANY PART THEREOF
SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM
OR BY ANY MEANS, ELECTRONIC OR MECHANICAL,
INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY
INFORMATION STORAGE AND RETRIEVAL SYSTEM,
WITHOUT THE WRITTEN PERMISSION OF DOLLAR &
EWERS ARCHITECTURE, INC. FOR OTHER PURPOSES
IN CONNECTION WITH THE PROJECT IS NOT TO BE
CONSIDERED AS PUBLICATION IN VIOLATION OF
DE&A COMMON LAW COPYRIGHT OR OTHER RESERVED RIGHTS.
COPYRIGHT


ISSUE DATE: SEPTEMBER 9, 2021
PROJECT NO.: 221249

SHEET NUMBER:

A101



SCHEMATIC MEZZANINE PLAN
SCALE: 1/8" = 1'-0"



SCHEMATIC FLOOR PLAN
SCALE: 1/8" = 1'-0"




File No.: **9-A-21-UR**

Date submitted: **8/23/2021**

These plans have not been reviewed by
Planning Staff and may not be finalized.

KNOX COUNTY PLANNING NUMBER 9-A-21-UR



ARCHITECTURE, INC.

111 E. Jackson Avenue • Suite 101
Knoxville, Tennessee • 37915
phone: 865-546-9374 • fax: 865-673-9028
e-mail: design@dollar-ewers.com



NO.	REVISIONS





USE ON REVIEW REQUEST PACKAGE FOR

A NEW OFFICE WAREHOUSE
HARRIS RD, KNOXVILLE, TN

SCHEMATIC FLOOR PLAN

C O P Y R I G H T
ALL DRAWINGS, SPECIFICATIONS AND COPIES THEREOF
FURNISHED BY DOLLAR & EWEERS ARCHITECTURE, INC.
ARE AND SHALL REMAIN THE PROPERTY OF DE&A, INC.
THEY ARE TO BE USED ONLY WITH RESPECT TO THIS PROJECT
AND ARE NOT TO BE USED WITH ANY OTHER
PROJECT. WITH THE EXCEPTION OF ONE CONTRACT SET
FOR EACH PARTY TO THE CONTRACT, SUCH DOCUMENTS ARE
TO BE RETURNED OR SURRENDERED TO DE&A, INC.
ON REQUEST AT THE COMPLETION OF THE WORK. SUBMISSION
DISTRIBUTION TO MEET OFFICIAL REGULATORY REQUIREMENTS
OR FOR OTHER PURPOSES IN CONNECTION WITH THE PROJECT
IS NOT TO BE CONSIDERED AS PUBLICATION IN DEROGATION
OF DE&A'S COMMON LAW COPYRIGHT OR OTHER RESERVED RIGHTS.
C O P Y R I G H T

ISSUE DATE:	SEPTEMBER 9, 2021
PROJECT NO.:	221249
SHEET NUMBER:	A201



File No.: 9-A-21-UR

Date submitted: 8/23/2021

These plans have not been reviewed by Planning Staff and may not be finalized.



ARCHITECTURE, INC.

111 E. Jackson Avenue • Suite 101
Knoxville, Tennessee • 37915
phone: 865-546-9374 • fax: 865-673-9028
e-mail: design@dollar-ewers.com



NO.	REVISIONS
△	
△	
△	
△	
△	

KNOX COUNTY PLANNING NUMBER 9-A-21-UR

USE ON REVIEW REQUEST PACKAGE FOR

A NEW OFFICE WAREHOSUE

HARRIS RD, KNOXVILLE, TN

SCHEMATIC ELEVATIONS

C O P Y R I G H T

ALL DRAWINGS, SPECIFICATIONS AND COPIES THEREOF FURNISHED BY DOLLAR & EWERS ARCHITECTURE, INC. ARE AND SHALL REMAIN THE PROPERTY OF DE&A, INC. THEY ARE TO BE USED ONLY IN CONNECTION WITH THE PROJECT AND ARE NOT TO BE USED WITH ANY OTHER PROJECT. WITH THE EXCEPTION OF ONE CONTRACT SET FOR EACH PARTY TO THE CONTRACT, SUCH DOCUMENTS ARE TO BE RETURNED OR DESTROYED ACCORDING TO DE&A, INC. ON REQUEST AT THE COMPLETION OF THE WORK. SUBMISSION OF THIS DRAWING FOR REVIEW OR FOR OTHER PURPOSES IN CONNECTION WITH THE PROJECT IS NOT TO BE CONSIDERED AS PUBLICATION IN VIOLATION OF DE&A, INC. COMMON LAW COPYRIGHT OR OTHER RESERVED RIGHTS.

C O P Y R I G H T

ISSUE DATE:	SEPTEMBER 9, 2021
PROJECT NO.:	221249
SHEET NUMBER:	

A501